



20 STAIR 2 - SECTION
1/4" = 1'-0"


16 STAIR 2 - SECTION
1/4" = 1'-0"



6 STAIR 2 - 3RD & 4TH FLOOR
1/4" = 1'-0"



7 STAIR 2 - 2ND FLOOR
1/4" = 1'-0"



8 STAIR 2 - 1ST FLOOR
1/4" = 1'-0"

- | # | NOTES |
|-----|---|
| 1. | SUBMIT CALCULATIONS STAMPED BY A REGISTERED ENGINEER. |
| 2. | PREFABRICATED METAL RAILING AND HANDRAIL. DESIGN AND SUBMIT SHOP DRAWINGS FOR OWNER'S APPROVAL PRIOR TO FABRICATION. |
| 3. | PREFABRICATED "DROP IN" METAL STAIR. |
| 4. | PREFABRICATED LANDING WITH CONCRETE FILL. |
| 5. | NON BEARING CONCRETE WALL (SSD). |
| 6. | BEARING CONCRETE WALL (SSD). |
| 7. | FRAMED 2x STUD WALL (SSD). |
| 8. | OUTLINE OF STAIR SHAFT WALL ABOVE. |
| 9. | 1" GYPCRETE OR FIRM-FILL OVER SOUND MAT, OVER 3/4" T&G PLYWOOD OVER 14" DEEP 4x2 MANUFACTURED FLOOR TRUSSES @ 16" O.C., WITH GLASS BATT INSULATION AND 5/8" GYPSUM BOARD ON RESILIENT CHANNEL, SEE A10.1. |
| 10. | 1" GYPCRETE OR FIRM-FILL OVER SOUND MAT, OVER 3/4" T&G PLYWOOD OVER 2x FLOOR JOIST (SSD). |
| 11. | 2x4 CEILING JOISTS @ 24" O.C.. |
| 15. | CONCRETE PT SLAB (SSD). |

THEOPHANOUS STRUCTURAL ENGINEERS BUILDINGS, BRIDGES, AND RELATED STRUCTURES ANALYSIS * DESIGN * PLAN CHECKING 75 Silverwood Drive, Lafayette, CA 94549 Tel: (925) 284-2822 Fax: (925) 284-9745 E-mail: rtheophanous@theo.com	
CLIENT: THEOPHANOUS FAMILY 1242 35th Ave Oakland, CA 94601 TEL: (925) 284-2822 Fax: (925) 284-9745	
PROJECT TITLE: FRUITVALE COMMONS	SHEET TITLE: STAIR 2 - PLAN & SECTION
REVISIONS	
CITY APPROVAL STAMP	
JOB NUMBER: J2002.060	DATE: 2/8/08
DRAWN BY: TO	CHECKED BY: NCT
SCALE (AS SHOWN)	
SHEET NUMBER: A6.2	
2 OF SHEETS	