





- # NOTATIONS
- F1 INDICATES FOOTING SCHEDULE TYPE 1. SEE FOOTING SCHEDULE FOR SIZE AND REINFORCEMENT
- GB1 INDICATES GRADE BEAM TYPE 1, SEE GRADE BEAM SCHEDULE FOR SIZE AND REINFORCEMENT
- C12-1 INDICATES CIRCULAR CONCRETE COLUMN, 12 IN COLUMN TYPE 1, SEE COLUMN SCHEDULE FOR SIZE AND REINFORCEMENT
- C1442-1 INDICATES RECTANGULAR CONCRETE COLUMN, 14 IN x 42 IN TYPE 1, SEE COLUMN SCHEDULE FOR SIZE AND REINFORCEMENT
- W8-524-518 WALL THICKNESS
INDICATES WALL, SEE WALL SCHEDULE FOR MORE INFORMATION
HOR. BAR SIZE AND SPACING
VERT. BAR SIZE AND SPACING
- 6-6-16 B BAR SIZE
BOTTOM, IF BLANK, TOP
- 6-6-18 BAR LENGTH
TOTAL NUMBER OF BARS
- 6-18 BAR SIZE
SPACING (in)
- + 33.34 INDICATES SLAB ELEVATION
- T.O.F. INDICATES TOP OF FOOTING
- T.O.C. INDICATES TOP OF CONCRETE
- C.J. INDICATES SAW CUT SLAB SHRINKAGE
CONTROL JOINTS SEE 14/SO.31
- CITY APPROVAL STAMP


 600DS125-27
 . . . INDICATES WALL FRAMED WITH 6" METAL STUDS TYPE DS WITH 1.25" WIDE FLANGE AND 27/1000 IN. WALL THICKNESS, SEE DWG 50.5 FOR WALL FRAMING.

 2X4
 . . . INDICATES WALL FRAMED WITH 2X4 WOOD STUDS

PROJECT TITLE: FRUITVALE COMMONS
1242 35th Ave Oakland, CA 94601

SHEET TITLE: SLAB ON GRADE PLAN

THEOPHANOUS FAMILY
75 SILVERWOOD DR LAFAYETTE, CA 94549
TEL:(925)284-2822 Fax:(925)284-9745